



### Customer

Banedanmark

### Location

Svendborg-Odense, Denmark

### Delivery date

August 2009

### Project summary

- 27,000 metres of track renewal
- 22,000 metres of ballast renewal
- 27,000 metres of packing
- transport & logistics

## Renewal of track Denmark

This project was done in international cooperation between Banekonsortiet and Strukton Rail.

### Activities

The project involved the renewal of circa 27,000 metres of track. The stations along the Svendborg-Odense line have double track; the rest of the railway line consists of single track.

### The activities include:

- 27,000 metres of track renewal with the P95 renewal train
- 22,000 metres of ballast renewal with the C750 ballast cleaner including 10 MFS wagons for the ballast removal
- 27,000 metres of packing (with CSM and switch packing machine) including ballast plough + stabiliser
- the transport was done using a Strukton Rail locomotive

