

## Project Svendborg - Odense



Client	Banedanmark
Country	Denmark
Location	Project Svendborg - Odense
Delivery date	09   08   2009
Size	Over 1 million EUR

This project is done in international cooperation between Banekonsortiet and Strukton Rail.  
Activities

The project involves the renewal of circa 27,000 metres of track. The stations along the Svendborg-Odense line have double track; the rest of the railway line consists of single track.

The activities include:

27,000 metres track renewal with the P95 renewal train

22,000 metres of ballast renewal with the C750 ballast cleaner including ten MFS wagons for the ballast removal

27,000 metres of packing (with CSM and switch packing machine) including ballast plough + stabiliser

transport is done using a Strukton Rail locomotive